BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division,

No.BBMP/EE/DD/Ten/01/2015-16, Date:04.01.2016 Indent No.20437

SCHEDULE-B

NAME OF WORK: Construction of culvert near Eagle bakery Ganesha Saw Mill road in Dasarahalli Ward no.15

Sl. No	Description of work	Unit	Qty	Rates Quoted by Contractor Ere Gowda S M		
				In Figures (Rs.)	In Words (Rs.)	Cont. AMOUNT
1	2	3	4	5	6	7
1	Earthwork excavation for foundation of buildings, water supply, sanitary, lines and electrical conduits either in pits or in trenches 1.5 m and above in width, in hard soil not exceeding 1.5m. in depth including dressing the bottom and and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead up to 50 m. after breaking of clods complete as per specfication & as per direction of Engineer-in-charge	Cum	23	288.0	Rupees Two Hundred Eighty Eight Only	6624.00
2	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @180 kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specfication & as per direction of Engineer-in-charge	Cum	3.45	5000.0	Rupees Five Thousand Only	17250.00
3	Providing and laying in position plain cement concrete of mix M20 with OPC cement @ 300kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.69cum and fine aggregates @ 0.43cum, with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, including cost all materials, labour, HOM of machinery, curing complete as per specfication & as per direction of Engineer-in-charge	~~Sqm~~ cum	5.86	5900.0	Rupees Five Thousand Nine Hundred Only	34574.00

Signature of the Contractor

Executive Engineer

4	Providing and laying in position reinforced cement concrete of Design mix M25 with OPC cement @ 340 kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.70cum and fine aggregates @ 0.47cum, with super plastisiser @ 3liters confirming to IS9103-1999 Reaffirmed-2008 at machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation for footings, pedastals, retaining walls, return walls, walls (any thickness) including attached pilasters, columnspillars, posts, struts, buttresses, bed blocks, anchor blocks & plinth etc., including cost of all materials, labour, HOM of machinery, curing, complete as per specifications. (Excluding cost of steel, fabrication & plastering charges) complete as per specfication & as per direction of Engineer-in-charge	Cum	7.2	6255.0	Rupees Six Thousand Two Hundred Fifty Five Only	45036.00
5	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for flat surface such as suspended floors, roofs, landings, balconies and likes, thickness above 200 mm including cost of all materials, labour complete as per specfication & as per direction of Engineer-in-charge	Sqm	24	400.0	Rupees Four Hundred Only	9600.00
6	Providing T.M.T. steel reinforcement for R.C.C. work including straightening cutting, bending, hooking, placing in position, lapping and (or welding wherever required, trying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specfication & as per direction of Engineer-in-charge	Tonne	1.03	70500.0	Rupees Seventy Thousand Five Hundred Only	72615.00
7	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 4 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading complete as per specfication & as per direction of Engineer-in-charge	Cum	23	79.0	Rupees Seventy Nine Only	1817.00
					Total	187516.00
					Percentage	-1.05%

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,

Signature of the Contractor

Executive Engineer

4	Providing and laying in position reinforced cement concrete of Design mix M25 with OPC cement @ 340 kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.70cum and fine aggregates @ 0.47cum, with super plastisiser @ 3liters confirming to IS9103-1999 Reaffirmed-2008 at machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation for footings, pedastals, retaining walls, return walls, walls (any thickness) including attached pilasters, columnspillars, posts, struts, buttresses, bed blocks, anchor blocks & plinth etc., including cost of all materials, labour, HOM of machinery, curing, complete as per specifications. (Excluding cost of steel, fabrication & plastering charges) complete as per specfication & as per direction of Engineer-in-charge	Cum	7.2	6255.0	Rupees Six Thousand Two Hundred Fifty Five Only	45036.00
5	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for flat surface such as suspended floors, roofs, landings, balconies and likes, thickness above 200 mm including cost of all materials, labour complete as per specfication & as per direction of Engineer-in-charge	Sqm	24	400.0	Rupees Four Hundred Only	9600.00
6	Providing T.M.T. steel reinforcement for R.C.C. work including straightening cutting, bending, hooking, placing in position, lapping and (or welding wherever required, trying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specfication & as per direction of Engineer-in-charge	Tonne	1.03	70500.0	Rupees Seventy Thousand Five Hundred Only	72615.00
7	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 4 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading complete as per specfication & as per direction of Engineer-in-charge	Cum	23	79.0	Rupees Seventy Nine Only	1817.00
					Total	187516.00
					Percentage	-1.05%

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,

Signature of the Contractor

Executive Engineer